

MAINTENANCE PLANNING GUIDELINES												01/2014																																					
ACTIVITY: Roadway & Bridge Safety Features (R227) MAJOR & MINOR						ACTION: Guard Cables																																											
DEFINITION: The time and expenses incurred for installing and maintaining guard cable along the roadway median and roadside obstacles																																																	
PURPOSE: Restore guard cable.																																																	
SCHEDULING: As needed.						<table><tr><td>J</td><td>F</td><td>M</td><td>A</td><td>M</td><td>J</td><td>J</td><td>A</td><td>S</td><td>O</td><td>N</td><td>D</td></tr><tr><td>A</td><td>E</td><td>A</td><td>P</td><td>A</td><td>U</td><td>U</td><td>U</td><td>E</td><td>C</td><td>O</td><td>E</td></tr><tr><td>N</td><td>B</td><td>R</td><td>R</td><td>Y</td><td>N</td><td>L</td><td>G</td><td>P</td><td>T</td><td>V</td><td>C</td></tr></table>								J	F	M	A	M	J	J	A	S	O	N	D	A	E	A	P	A	U	U	U	E	C	O	E	N	B	R	R	Y	N	L	G	P	T	V	C
						J	F	M	A	M	J	J	A	S	O	N	D																																
A	E	A	P	A	U	U	U	E	C	O	E																																						
N	B	R	R	Y	N	L	G	P	T	V	C																																						
RECOMMENDED EQUIPMENT: <ul style="list-style-type: none">TruckPost DriverTraffic Control Equipment; (See EPG 616.23 Traffic Control for Field Operations)						RECOMMENDED PROCEDURE: <ol style="list-style-type: none">Contact Dig Rite and others to mark utilities.Place traffic control devices as needed.Remove damaged cable and post.Install new post and cable.Remove traffic control devices.																																											
RECOMMENDED MATERIAL: <ul style="list-style-type: none">CablePostAnchors																																																	
SAFETY: Refer to the Comprehensive Safety Program sharepoint portal . Wear all appropriate PPE. Refer to the Risk Based Assessment for additional information.																																																	
OTHER CONSIDERATIONS:																																																	
REFERENCES: Missouri Standard Specifications for Highway Construction , Section 606																																																	